

TECHNICAL REPORT STANDARD PAGE

1. Report No. FHWA/LA.88/313		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle Thin Bonded Overlay and Surface Laminates - Construction		5. Report Date February 1998		6. Performing Organization Code	
		7. Author(s) Craig Duos, P.E.		8. Performing Organization Report No. 97-2C	
9. Performing Organization Name and Address Louisiana Transportation Research Center 4101 Gourrier Avenue Baton Rouge, LA 70808		10. Work Unit No.		11. Contract or Grant No. DTFH71-97-TBO-LA-13	
		12. Sponsoring Agency Name and Address Louisiana Transportation Research Center 4101 Gourrier Avenue Baton Rouge, LA 70808		13. Type of Report and Period Covered Interim Report	
		14. Sponsoring Agency Code			
15. Supplementary Notes Conducted in Cooperation with the U.S. Department of Transportation, Federal Highway Administration					
16. Abstract In 1997, a Portland Cement Concrete (PCC) Thin Bonded Overlay (TBO) using a one and one-half inch thickness was placed on two bridges, I-10 at the Bonne Carre Spillway and US 90 at Bayou Des Allemands, under the Applied Research & Technology Program of the Intermodal Surface Transportation Efficiency Act (ISTEA), section 6005(e)(7). Section 6005 provides funding for the overlay of deteriorating roadways and/or bridge decks utilizing a thin bonded overlay. The two sections of bridge decks that the Department of Transportation and Development (DOTD) overlaid are five spans in the east bound lane of I-10 over the Bonne Carre Spillway and eight spans in the east bound lane of US 90 over Bayou Des Allemands, both in St. Charles Parish. These two sites will be used to evaluate the feasibility of and costs and benefits associated with the repair, rehabilitation, and upgrading of highways and bridges with respect to TBOs and surface laminates. This report documents construction activities.					
17. Key Words Thin Bonded Overlay			18. Distribution Statement Unrestricted. This document is available through the National Technical Information Service, Springfield, VA 21161.		
19. Security Classif. (of this report)		20. Security Classif. (of this page)		21. No. of Pages	
				22. Price	



THIN BONDED OVERLAY AND SURFACE LAMINATES - CONSTRUCTION

by

CRAIG DUOS, P.E.

LTRC PROJECT NO. 97-2C
STATE PROJECT NOS. 005-08-0047 & 450-14-0054
FEDERAL AID PROJECT NOS. BRN-11-9(004) & IM-10-4 (156)212

Conducted by

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
LOUISIANA TRANSPORTATION RESEARCH CENTER

in cooperation with

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the Louisiana Department of Transportation and Development or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

February 1998



ABSTRACT

In 1997, a Portland Cement Concrete (PCC) Thin Bonded Overlay (TBO) using a one and one-half inch thickness was placed on two bridges, I-10 at the Bonne Carre Spillway and US 90 at Bayou Des Allemands, under the Applied Research & Technology Program of the Intermodal Surface Transportation Efficiency Act (ISTEA), section 6005(e)(7). Section 6005 provides funding for the overlay of deteriorating roadways and/or bridge decks utilizing a thin bonded overlay.

The two sections of bridge decks that the Department of Transportation and Development (DOTD) overlaid are five spans in the east bound lane of I-10 over the Bonne Carre Spillway and eight spans in the east bound lane of US 90 over Bayou Des Allemands, both in St. Charles Parish. These two sites will be used to evaluate the feasibility of and costs and benefits associated with the repair, rehabilitation, and upgrading of highways and bridges with respect to TBOs and surface laminates. This report documents construction activities.




TABLE OF CONTENTS

ABSTRACT	v
TABLE OF CONTENTS	vii
INTRODUCTION	1
PROJECT LOCATION	3
PRE-CONSTRUCTION	3
CONSTRUCTION	4
SURFACE PREPARATION	6
OVERLAY	7
POST CONSTRUCTION EVALUATION	9
PERFORMANCE EVALUATION	14
CONCLUSIONS	15
APPENDIX A	17
APPENDIX B	21
APPENDIX C	27
APPENDIX D	33



INTRODUCTION

In 1997, a Portland Cement Concrete (PCC) Thin Bonded Overlay (TBO) using a one and one-half inch thickness was placed on two bridges, I-10 at the Bonne Carre Spillway and US 90 at Bayou Des Allemands, under the Applied Research & Technology Program of the Intermodal Surface Transportation Efficiency Act (ISTEA), section 6005(e)(7). Section 6005 provides funding for the overlay of deteriorating roadways and/or bridge decks utilizing a thin bonded overlay.

The two sections of bridge decks that the Department of Transportation and Development (DOTD) overlaid are five spans in the east bound lane of I-10 over the Bonne Carre Spillway and eight spans in the east bound lane of US 90 over Bayou Des Allemands, both in St. Charles Parish. These two sites will be used to evaluate the feasibility of and costs and benefits associated with the repair, rehabilitation, and upgrading of highways and bridges with respect to TBOs and surface laminates. This report documents construction activities.



Project Location and Contractor

The research projects are located in St. Charles Parish on I-10 and US 90 over the Bonne Carre Spillway and Bayou Des Allemands. Maps with exact project locations are shown in appendix A.

The contract for these projects were awarded to Coastal Bridge Company, Inc., of Baton Rouge, Louisiana.

Preconstruction

Prior to construction, conditions at each site were evaluated. Falling Weight Deflectometer(FWD) measurements were taken as well as chloride profiles (Appendix D). Additionally, a preinstallation photographic record and pavement distress survey were performed.

The pavement distress survey conducted on the two project sections followed the guidelines outlined in the *Distress Identification Manual for the Long-Term Pavement Performance Project* (appendix D). The only distress identified within the sections was scaling. Scaling refers to the deterioration of the upper concrete slab surface, resulting in the loss of surface mortar. Most of the scaled areas had been patched. The total area of the I-10 project was 11,700 square feet with 6,784 square feet exhibiting scaling (58 %). The total area of the US 90 project was 15,360 square feet with 3,555 square feet exhibiting scaling (23 %).

Other preconstruction activities included a test pour, by and at the contractor's expense, which

was used to determine the mixing sequence, workability, curing, and finishing characteristics of the mix.

Construction

The materials and mix specifications were as follows:

Cement Type: Type I, IB, III conforming to DOTD Standard Specifications, Section 901, shall be used.

Cement Content: 6.5 bags of cement per cubic yard.

Silica Fume: Eight percent (equivalent dry weight) by weight of cement. Force 10,000 densified silica fume by Grace Construction Products in 25 pound bags or approved equal shall be used. The densified silica fume shall contain a minimum of 90 percent SiO₂, a maximum of one percent SO₃, a maximum of three percent loss on ignition(LOI), a maximum alkali content of NA₂O of 1.5 percent, and a maximum moisture content of three percent.

Fiber Reinforcement: Fibers shall be monofilament consisting of 100% virgin polypropylene. The fibers shall be 3/4 inch in length and shall be included in the mix at a rate of two pounds per cubic yard. The approved fibers shall be Grace Microfibers by Grace Construction Products or an approved equal.

Water/Cementitious ratio: The ratio shall be 0.40 maximum(including any water in the admixtures).

- Air Content:** Between three and five percent.
- Slump:** Between three and five inches.
- Strength:** A 28 day compressive strength of 6000 psi.
- Coarse Aggregate:** Grade F, with ratio of coarse to fine aggregate of 60/40. All aggregates shall conform to Subsection 1003.02 of the 1992 *Louisiana Standard Specifications for Roads and Bridges*.
- Admixtures:** Admixtures shall be used in quantities consistent with the manufacturer's recommendations and shall be added at the concrete plant. Additional water reducers may be added at the job site when required. Air entraining agents and set controlling admixtures may also be used. All admixtures shall be from the Qualified Products List (QPL) and shall be compatible with the other admixtures used.

The actual mix design is included in appendix C.

A request concerning the batching operation was made by the contractor at the pre-construction conference. The owner of Coastal Bridge Co., Inc., requested the following mixing sequence: mix aggregates would be placed into the drum mixer of the truck at La Farge redi-mix plant and, after arriving at the site, cement, admixtures and water would be added. The W.R. Grace representative advised that with proper mixing time this would not be a problem. DOTD personnel also felt that the proposed mixing sequence would not be a problem and would also provide maximum working time for the concrete, so the request was granted.

Surface Preparation

I-10 at Bonne Carre

Concrete was to be removed to a depth of one and one-half inches. The contract provided the contractor with several options for concrete removal, grinding, hydro-blasting, or shot blasting. The contractor choose the grinding option, except in the immediate vicinity of the end dams which was done by rotary impact hammers. Grinding was successful until the fourth span when reinforcing steel was encountered at a depth of one inch. At this time grinding was halted and damaged steel was repaired as per contract specifications. A decision was made by the contractor's representative and DOTD project personnel to use hydro-blasting to remove the remaining surface concrete from spans four and five. However, hydro-blasting was too slow and the contractor, with the Project Engineer's approval, used chipping guns to remove the remaining concrete from span four. After removal of the top one and one-half inches of concrete, the scarified surface was cleaned by air blasting.

US 90 at Bayou Des Allemands

Concrete was to be removed to a depth of one and one-half inches and the contract provided the contractor with several options for concrete removal, grinding, hydro-blasting, or shot blasting. The contractor again chose the grinding option, except in the immediate vicinity of the end dams which was done by rotary impact hammers. The Bayou Des Allemands project was in worse condition than I-10 at Bonne Carre. Practically the entire surface area was scaled and laminated to a depth which exceeded the one and one-half inches the overlay was intended to address and in a few areas the depth of deterioration exceeded three inches. As a result, grinding was not

effective in removing all of the deteriorated concrete. A decision was made to use hydro-blasting in order to maintain steel reinforcing integrity; this method was too slow, so chipping guns were used. After removal of the deteriorated concrete, the scarified surface was cleaned by air blasting.

Overlay

I-10 at Bonne Carre Spillway

Overlay operations began at 7:35 a.m. on July 29, 1997. One lane was closed for construction while traffic was channeled to the other. There was some concern about the vibrations caused by traffic, but maintaining traffic did not cause excessive vibrations. As per the pre-construction agreement, the concrete truck had already been charged with fine and coarse aggregate at La Farge's plant. Fibers, admixtures (air entrainment, set retarders, high range water reducers and, silica fume), cement, and water (adjusted for moisture in the fine and coarse aggregate) were added at the job site and mixed thoroughly. Mixing was usually completed by 9:00 a.m.

During mixing, the deck was prepared to receive the overlay by air blasting and water soaking. Immediately prior to placement of the overlay, a bonding grout consisting of equal parts Portland Cement and concrete sand with a water/cement ratio of 0.44 was mixed according to contract specifications to form a slurry and broomed onto the surface. At no time was it necessary for the bonding grout to be re-tempered.

The placement of concrete was usually completed between 30 and 45 minutes after mixing was complete. A Baker Screed with external vibrators was used to initially level and consolidate the

concrete. The admixture representative advised that the mix should not be over vibrated and due to the thinness of the overlay all parties agreed that external vibration was sufficient to achieve proper consolidation. Temperatures during overlay operations ranged from 70° F to 92° F, wind speeds were between 5 and 10 mph under partly cloudy skies. Concrete temperatures never exceeded 90° F, except for span 245 which reached 94° F, but compressive strengths still exceeded 6000 psi. Texturing was performed by burlap drag and continuous fogging was used during and immediately after finishing until the overlay could support pre-wetted strips of burlap. The burlap was kept wet for 42 hours or until the concrete had achieved a compressive strength of 3200 psi.

Quality control and acceptance testing was performed by DOTD District 02 personnel with additional testing performed by Louisiana Transportation Research Center (LTRC) and DOTD Materials and Testing personnel. These tests are presented in appendix D. Quality control testing consisted of slump, air content, and temperature, while acceptance was based on compressive strength tests. Additional testing performed by LTRC and the Materials Section included chloride content, half cell potentials, chloride penetrability, flexure strength, splitting tensile, tensile bond strength, chain drag, skid tests, and pre-installation and post-installation Falling Weight Deflectometer which are also included in appendix D.

Although the contractor's personnel were not completely familiar with the mixing, finishing, and curing characteristics of silica fume concrete, the overlay was placed without event. The only problem during the entire project was mechanical in nature. On span four, the screed broke down

after three passes and the final finish was done by hand. No additional vibration was done as the project engineer felt that the concrete had been properly consolidated after the initial passes with the screed's external vibrators.

U.S. 90 at Bayou Des Allemands

Bayou Des Allemands was constructed after the Bonne Carre was completed. The same construction sequence was followed on the Des Allemands project except for the finish. Instead of a burlap drag finish the project engineer requested a broom finish. Overlay operations began on September 8, 1997, and continued until November 21, 1997. All spans were poured in the morning except for span six which was poured between 1:40 p.m. and 2:00 p.m.. Wind speeds ranged from 5 to 20 mph under partly cloudy skies, except for span six which was poured under overcast skies. Temperatures ranged from 40° F to 92° F during overlay operations. Concrete temperatures approached 90° F but never exceeded it. Continuous fogging was again employed until wetted burlap could be placed. There were no problems with equipment and placement of the overlay.

Post Construction Evaluation

Construction of both projects went as well as could be expected given the temperamental nature of the mix and the lack of experience, on the contractor's part, with silica fume mixes. The only problems encountered during pre-overlay operations was with milling. Reinforcement steel was not at a consistent depth throughout the structure and damage by milling operations had to be repaired. This occurred in span 248 of the Bonne Carre project and span seven of the Bayou Des

Allemands project.

During the overlay phase of construction the only problem encountered was with the screed on the Bonne Carre project.

There was a problem with low breaks on both projects. Compressive strengths on span 246 on Bonne Carre right of center line were low with an average compressive strength of 5736 psi. This was due to the contractor exceeding the water/cementitious ratio. Spans seven and eight left of the center line, on Bayou Des Allemands, had average breaks of 5729 psi and 4132 psi, respectively. Nothing in the daily reports, plant reports for moisture, or batch proportions showed up which would explain the low breaks for spans seven and eight. Concrete temperature, slump, and air were all within allowable tolerances, and moisture in the aggregates had been accounted for. However, there were discrepancies in the testing procedures worth noting. When LTRC made and tested cylinders for compressive strength on spans 246 on Bonne Carre right of centerline and span eight left of centerline on Bayou Des Allemands, we arrived at different results than the District 02 laboratory. The cylinders LTRC personnel made and tested for span 246 had an average compressive strength of 5920 psi and span eight had an average compressive strength of 6859 psi. When compared to District 02 tests, the cylinders from span 246 are similar and can be explained by the high water/cementitious ratio used, but the cylinders from span eight are quite different. There is a difference of 2727 psi between cylinders made from the same batch. Also, District 02's seven day breaks, for span eight, were higher than the 28 day breaks for span eight. Seven day breaks averaged 5553 psi, while 28 day breaks averaged 4132 psi. It's

believed that the discrepancies are in the fabrication or testing of the cylinders and not, in this case, with the mix proportions.

A chain drag test and impact test performed on 5' x 5' grids revealed no delaminated sections.

Following construction of the microsilica concrete overlay on the project sections of I-10 and US 90, friction testing was conducted. Friction tests were run on US 90 on January 23, 1998, and on I-10 on January 28, 1998. Pavement surface testing for friction, or skid resistance, was done on a test section and a control section for each project site. The test section for each site was the section of roadway with the microsilica concrete overlay, while the control section for each site was the original section of roadway adjacent to the test section.

The data collected includes friction values obtained according to ASTM E 274-90, the *Standard Test Method for Skid Resistance of Paved Surfaces Using a Full-Scale Tire*. The friction values are reported for two tire types, the treaded (standard rib) tire (ASTM E 501-94 Standard Specification) and the blank (standard smooth) tire (ASTM E 524-88 Standard Specification). Both tire types measure the frictional properties of the pavement. However, the treaded tire is more responsive to changes in the microscopic surface texture, while the blank tire is more responsive to changes in the obvious and visible texture that allows water to escape from between the tire and road. All friction tests were run at a vehicle speed of 40 mph \pm 1 mph and under simulated wet weather conditions.

Friction testing data for the project sections is displayed in tables in appendix D. Each table contains log miles and skid numbers. The log mile is a linear distance location along a route within a particular highway control section, which is within a parish. The I-10 project is located in highway control section 450-14 in St. Charles Parish. The US 90 project is located in highway control section 005-08 in St. Charles Parish. The skid number is a measurement of skid resistance of a wet pavement surface and can also be viewed as a measurement of friction between a tire and a wet pavement surface.

Friction testing on I-10 yielded an average skid number of 42.6 for the test (microsilica) section and 39.6 for the control section using the treaded tire and an average skid number of 26.0 for the test section and 22.2 for the control section using the blank tire. Friction testing on US 90 yielded an average skid number of 40.7 for the test section and 45.1 for the control section using the treaded tire and an average skid number of 22.3 for the test section and 24.1 for the control section using the blank tire.

The data indicates that skid numbers for the test (microsilica) sections are comparable with that for the control sections at both project sites. Thus, the construction of the microsilica concrete overlays did not significantly affect the surface frictional properties of the pavement.

Structural capacity testing was conducted on the project sections of I-10 and US 90 before and after construction of the microsilica concrete overlay. The structural testing was performed by means of deflection testing of the concrete slab surface with a Dynatest 8000 Falling Weight

Deflectometer. Deflections were measured in thousandths of an inch (mils) when a nondestructive falling load of about 18,000 pounds (lbs) was applied by the FWD at various project locations. The maximum deflection was obtained by the sensor located at the center of the load plate. Deflection testing was linearly located five feet ahead of the joint and also at the midspan of each concrete bridge deck span. The testing was also vertically aligned to not be directly over deck support girders to enhance deflections under heavy loads.

For the I-10 section, structural tests were run on July 10, 1997, before the overlay and on August 11, 1997, after the overlay. The five spans were referenced as spans A, B, C, D, and E traveling eastbound. For the US 90 section, structural tests were run on July 11, 1997, before the microsilica construction and on February 12, 1998, after the microsilica construction. The eight spans were referenced as spans A, B, C, D, E, F, G, and H traveling eastbound. Each test located five feet ahead of the joint was referenced as No.1, while each test located at the midspan was referenced as No.2.

Results of the deflection testing for both project sections are displayed in appendix D. Smaller deflections indicate higher structural capacity of the pavement deck. As expected, deflections were higher at midspan compared to that five feet ahead of the joint. This was due to less structural support beneath the midspan locations. A vivid picture of the midspan deflection results can be seen on the attached bar graphs (appendix D). Maximum midspan deflections ranged from 13.9 to 18.2 mils before the overlay and from 14.5 to 16.0 mils after the overlay for the I-10 project. Maximum midspan deflections ranged from 23.6 to 39.6 mils before the

overlay and from 23.1 to 27.1 mils after the overlay for the US 90 project.

The results of the deflection testing on both project sections indicate that the structural capacity of the bridge decks is not affected by the microsilica concrete overlay.

Performance Evaluation

Each site will be evaluated annually, for five years, on or near the date the projects were accepted, December 11. As a minimum, a visual site inspection will be done once a year to document changes if any. Also, any unusual climatic conditions will be documented. This site usually does not experience problems with icing; however, if it does occur and the bridge is salted this will also be documented.


CONCLUSIONS

The overlay is in place and performing well. There were no unexpected problems with the mix, except those already noted. Chain drag and tensile bond tests showed no delaminations and adequate bonding between the existing bridge deck and the overlay. The spans, with low compressive strengths will bear watching; however, it appears from project records that the mix proportions were correct and that the problem was in fabrication or testing of the cylinders.





APPENDIX A





VICINITY MAP





S.P. NO. 005-08-0047

APPENDIX B





PLAN VIEW OF US 90 DECK OVERLAY PROJECT





Bayou Des Allemonds, Eastbound
STATE PROJECT No. 005-08-0047

PLAN VIEW OF I-10 DECK OVERLAY PROJECT





Bonnet Carre, eastbound
STATE PROJECT No. 450-14-0054

PAVEMENT DISTRESS SURVEY BEFORE CONSTRUCTION I-10 PROJECT SECTION




All pavement distress is scaling.
Most scaled areas are patched.

PAVEMENT DISTRESS SURVEY BEFORE CONSTRUCTION US 90 PROJECT SECTION



All pavement distress is scaling.
Most scaled areas are patched.

APPENDIX C



MATT MENU SELECTION 30

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
PORTLAND CEMENT CONCRETE MIX DESIGN

DOTD 10224754
REV. 8/80

PROJECT NO. 17109-114-010114 MATERIAL USE P or S TYPE/CLASS 172-1
 PLANT CODE 6111 MATERIAL CODE 613 MAX DESIGN NO. 613
 Slip Form Parking Reading Method: 11 1 - Trench Method, 2 - Compact Method, 3 - Also Other
 F.A.P. 11 Project Name T-10 Bridge Concrete Bridge Deck Resurfacer

MATERIALS

Material	Source Code	Company Name	Location	Material Code	Alkali Reactivity	Specific Gravity	Absorption Factor	Product Name
Cement	<u>102514</u>	<u>Holston</u>	<u>Thibodaux, LA.</u>	<u>11516</u>	<input type="checkbox"/>	<u>3.15</u>	<u>1.0</u>	<u>Chauxville 1000</u>
Fly Ash	<u>111114</u>	<u>La Industries</u>	<u>Isaiah</u>	<u>11111</u>	<input type="checkbox"/>	<u>2.65</u>	<u>1.0</u>	<u>Durlock 19</u>
Fine Aggregate	<u>111114</u>	<u>La Industries</u>	<u>Isaiah</u>	<u>11111</u>	<input type="checkbox"/>	<u>2.65</u>	<u>1.0</u>	<u>France 10000</u>
Coarse Aggregate 1	<u>111114</u>	<u>La Industries</u>	<u>Isaiah</u>	<u>11111</u>	<input type="checkbox"/>	<u>2.65</u>	<u>1.0</u>	<u>Micro 516.62</u>
Coarse Aggregate 2	<u>111114</u>	<u>La Industries</u>	<u>Isaiah</u>	<u>11111</u>	<input type="checkbox"/>	<u>2.65</u>	<u>1.0</u>	
Water Reducer	<u>111114</u>	<u>GRACE</u>	<u>Normal Set</u>	<u>12610</u>	<input type="checkbox"/>	<u>1.2</u>	<u>1.0</u>	
Air Entrainer	<u>111114</u>	<u>GRACE</u>	<u>Chloridiz</u>	<u>2517</u>	<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	
Set Accelerator	<u>111114</u>	<u>GRACE</u>			<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	
Superplasticizer	<u>111114</u>	<u>GRACE</u>			<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	
Special Additive A	<u>111114</u>	<u>GRACE</u>			<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	
Special Additive B	<u>111114</u>	<u>GRACE</u>			<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	
Special Additive C	<u>111114</u>	<u>GRACE</u>			<input type="checkbox"/>	<u>1.0</u>	<u>1.0</u>	

Mixing Water: 1-City, 2-Well, 3-Other

Mix Proportions For One Cubic Yard of Concrete

Material	Quantity	UNIT
Cement	<u>3108</u>	lbs
Fly Ash	<u>00</u>	lbs
Fine Aggregate (SSD)	<u>72788</u>	lbs
Coarse Aggregate 1 (SSD)	<u>109306</u>	lbs
Coarse Aggregate 2 (SSD)	<u>000</u>	lbs
Water	<u>40764</u>	gal
Water Reducer	<u>0.00</u>	ozs
Air Entrainer	<u>1.08</u>	ozs
Set Accelerator	<u>0.00</u>	ozs
Superplasticizer	<u>0.1278</u>	ozs
Special Additive A	<u>0.3490</u>	ozs
Special Additive B	<u>0.0252</u>	ozs
Special Additive C	<u>0.0</u>	ozs
Total	31.6	UNIT (lbs, gal, ozt)

Contractor: Seastal Bridge Co (0971)
 Submitted By: Roy Overall
 Date Submitted: Cent. Conc. Test 859-2977

Departmental Use
 Yield: 1217 Cubic Feet
 Cement Factor: 7110 Bags/Cubic Yard
 Fly Ash: 1018 % By Weight
 Water-Cement Ratio: 4.115 Gallons/Bag
 Water-Cement Ratio: 0.410 By Weight
 Cement with 0.6% or less Alkali: 115

Received: _____ Code _____ Date _____
 Project Engineer: _____
 District Laboratory Engineer: _____ Code _____ Date _____

ACCEPTED REJECTED

Acceptance based on mix proposal meeting specification requirements for yield, cement factor, water-cement ratio, materials sources, cement type, fly ash type, admixture types, special additives and MATT Codes.

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
PORTLAND CEMENT CONCRETE MIX DESIGN

PROJECT NO. 14150-141-10054
MATERIAL USE [S] P or S
MATERIAL CODE 1427 TYPE/CLASS
MIX DESIGN NO. 011
Mixing Method: [U] 1 - 1 min. 2 - 2 min. 3 - 3 min.

Project Name I-10 Bayou Corne Safety Bridge Replacement

Source Code	Company Name	Location	Material Code	Alkali Reactive	Specific Gravity	Absorption Factor	Product Name
10254	Holman	Theriot A1	1514	[M]	1.011	19.15	Ducobal 17
1112	LA Industries	Isabell	11210	[M]	21.1613	21.15	Ducobal 1000
11312	LA Industries	Isabell	1111	[]	21.0511	19.11	Ducobal 19
15106	GRACE	Normal Set	1111	[]	1.011	19.11	Escol 10000
15210	GRACE	Chloride	1111	[]	1.011	19.11	Micafibers
1111	GRACE		2610	[]	1.011	19.11	Elipaste
1111	GRACE		2511	[]	1.011	19.11	
1111	GRACE		1191	[]	1.011	19.11	

Mixing Water: [] 1-civ, 2-well, 3-Other

Mix Proportions For One Cubic Yard of Concrete	UNIT
Cement	16111 lbs
Fly Ash	1110 lbs
Fine Aggregate (SSD)	11110 lbs
Coarse Aggregate 1 (SSD)	11111 lbs
Coarse Aggregate 2 (SSD)	11110 lbs
Water	21118 gal
Water Reducer	111010 ozs
Air Entrainer	111010 ozs
Set Accelerator	1131010 ozs
Superplasticizer	1111010 ozs
Special Additive A	1131010 ozs
Special Additive B	1131010 ozs
Special Additive C	20101010 ozs

Contractor Crystal Bridge Co (0971)
 Submitted By Ray Owen 11 Coet Core Tech (504)
 Date Submitted 352-0653

Yield 27
 Cement Factor 21.19
 Fly Ash 10.8
 Water-Cement Ratio 4.15
 Water-Cement Ratio 1.19
 Cement with 0.6% or less Alkalies required [N]

Departmental Use
 Received []
 Project Engineer []
 District Laboratory Engineer []

Accepted [] Rejected []

Acceptance based on mix proposal meeting specification requirements for yield, cement factor, water-cement ratio, materials sources, cement type, fly ash type, admixture types, special additives and MATT Codes.

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
PORTLAND CEMENT CONCRETE MIX DESIGN

PROJECT NO. 17151A-114-100574
 PLANT CODE 1021511
 Slab Form Paving
 F.A.P. [W]
 MATERIAL USE [] P or S
 MATERIAL CODE 1524
 MIX DESIGN NO. 1012
 Mixing Method: []
 Project Name: 1021511-100574-114-100574
 Project Location: Bridge

MATERIALS

Source Code	Company Name	Location	Material Code	Alkali Reactive	Specific Gravity
1021511	Holman	Theodore, AL	1516	[]	[]
[]	[]	[]	[]	[]	[]
1021511	La Industrial	Isabell	1519	[]	2.108
1021511	La Industrial	Isabell	1517	[]	2.278
[]	[]	[]	[]	[]	10.9242
[]	[]	[]	[]	[]	0.00
151916	Grace	Normal Set	[]	[]	2.0630
151810	Grace	Chloride	[]	[]	0.0209
[]	[]	[]	[]	[]	1.08
[]	[]	[]	[]	[]	0.00
[]	[]	[]	[]	[]	0.1378
[]	[]	[]	[]	[]	0.3490
[]	[]	[]	[]	[]	0.0352
[]	[]	[]	[]	[]	0.00

Mixing Water: Source of Supply [] 1-City, 2-well, 3-Other

Mix Proportions For One Cubic Yard of Concrete

Cement	3,108	lbs
Fly Ash	0.0	lbs
Fine Aggregate (SSD)	7,278	lbs
Coarse Aggregate 1 (SSD)	10,924.2	lbs
Coarse Aggregate 2 (SSD)	0.00	lbs
Water	206.30	gal
Water Reducer	0.0209	ozs
Air Entrainer	1.08	ozs
Set Accelerator	0.00	ozs
Superplasticizer	0.1378	ozs
Special Additive A	0.3490	ozs
Special Additive B	0.0352	ozs
Special Additive C	0.00	ozs

31.6

UNIT (lbs, gal, ozs)

Contractor: Crystal Bldgs Co (0971)
 Submitted By: Ray Queenall
 Date Submitted: Sept 3, 1963

Yield 271.00
 Cement Factor 11.10
 Fly-Ash S.F. 0.0
 Water-Cement Ratio 4.15
 Cement with 0.8% or less Alkalies required 11.14

Received []
 Project Engineer []
 Code []
 ACCEPTED []
 REJECTED []
 District Laboratory Engineer []
 Code []

Acceptance based on mix proposal meeting specification requirements for yield, cement factor, water-cement ratio, materials sources, cement type, fly ash type, admixture types, special additives and MATT Code.

% Vol. 3.108
 0
 7.278
 10.9242
 0
 3.8532
 0.0209
 1.08
 0
 0.1378
 0.3490
 0.0352
 0.208
 26.9958



APPENDIX D



I-10 @ BONNET CARRE SPILLWAY- COMPRESSIVE STRENGTH, psi								
DISTRICT O2 RESULTS					LTRC RESULTS			
SPAN	RT OF CENTERLINE		LT OF CENTERLINE		RT OF CENTERLINE		LT OF CENTERLINE	
	7 DAY	28 DAY	7 DAY	28 DAY	24 HRS.	28 DAY	24 HRS.	28 DAY
245	6870	7599	5349	6384			3422	6879
246	4507	5736	5460	6936	2515	5920	2702	6878
247	5732	6847	5959	7539	3074	7033		
248	5501	7479	6073	7118	2599	7619		
249	6057	6252	4031	6208				

US 90 @ BAYOU DES ALLEMANDS - COMPRESSIVE STRENGTH, psi								
DISTRICT O2 RESULTS					LTRC RESULTS			
SPAN	RT OF CENTERLINE		LT OF CENTERLINE		RT OF CENTERLINE		LT OF CENTERLINE	
	7 DAY	28 DAY	7 DAY	28 DAY	24 HRS.	28 DAY	24 HRS.	28 DAY
1		7430	3107	6812				
2	4864	7413	6224	6387			3757	7533
3	5244	7220	5347	6922			827	6189
4	5146	7395	6336	7347			3346	6943
5	5087	7468	5856	6720				
6	5493	7899	5032	7280	1817	8406		
7	4965	7085	4728	5729	2994	6683		
8	3866	7497	5553	4132	2857	7989	2905	6859

Profilograph testing



STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
P. O. Box 94245
Baton Rouge, Louisiana 70804-9245



M. J. "MIKE" FOSTER, JR.
GOVERNOR

FRANK M. DENTON
SECRETARY

September 3, 1997
(504) 437-3111

S.P. NO. 005-08-0047 AND 450-14-0054
F.A.P. NOS. BRN-11-9(004) AND IM-10-4(156)212
U.S. 90 DECK OVERLAY (BAYOU DES ALLEMANDS) AND
I-10 DECK OVERLAY (BONNET CARRE)
ROUTES U.S. 90 AND I-10
ST. CHARLES PARISH

MEMORANDUM TO:

Mr. Ozzie Hansen

RE: Profilograph Testing for I-10 EB at Bonne Carre Spillway

Here are the results of profilograph testing on the bridge deck.

Please note the consistent dips at the joints - not necessarily indicative of the inherent surface rideability of the material.

The 60' panels were milled and overlaid with high strength silica fume concrete.

These results are for information only.

Luanna Cambas
District Laboratory Engineer

LC/ccb

cc: Mr. Frank Gradsky
Mr. Craig Duos
Mr. Bobby Overall
Mr. Brian Buckel

REPORT OF PROFILOGRAPH TRACE

PROJECT NO: <u>005-08-0047</u>	LOT NO: <u>EASTBOUND</u>
FROM STATION: _____	TO STATION: _____
FROM STATION: _____	TO STATION: _____

PAVEMENT TYPE: PCC PAVING ASPHALTIC CONCRETE
 WHEELPATH TYPE: TRAVEL LANE 10' OR WIDER SHOULDER
 EVALUATED FOR: INFO ACCEPTANCE (DOTD) QUALITY CONTROL (CONTR)

SPECIFICATIONS FOR LOT: INFORMATION ONLY

CALCULATIONS:

(1) ROADWAY: RIGHT LANE LOCATION: RIGHT WHEEL PATH
 LENGTH OF TRACE: 322 FT/5280 = 0.061 MILE
 PROFILE INDEX: 1.90 IN/ 0.061 MILE = 31.1 IN/MILE
WITHOUT EXCEPTIONS

(2) ROADWAY: RIGHT LANE LOCATION: RIGHT WHEEL PATH
 LENGTH OF TRACE: 222 FT/5280 = 0.042 MILE
 PROFILE INDEX: .60 IN/ 0.042 MILE = 14.3 IN/MILE
WITH EXCEPTIONS 100' USED FOR EXCEPTION

(3) ROADWAY: RIGHT LANE LOCATION: LEFT WHEEL PATH
 LENGTH OF TRACE: 322 FT/5280 = 0.061 MILE
 PROFILE INDEX: 1.30 IN/ 0.061 MILE = 21.3 IN/MILE
WITHOUT EXCEPTIONS

(4) ROADWAY: RIGHT LANE LOCATION: LEFT WHEEL PATH
 LENGTH OF TRACE: 222 FT/5280 = 0.042 MILE
 PROFILE INDEX: .65 IN/ 0.042 MILE = 15.5 IN/MILE
WITH EXCEPTIONS 100' USED FOR EXCEPTION

AVG. PROFILE INDEX: (Average of tests for lot) = _____ IN/MILE

TESTED BY:

CHECKED BY: Warren A. Hester

DATE: _____

DATE: 8-13-97

DESCRIPTION	TEST SPAN #1	TEST SPAN #2	TEST SPAN #3	TEST SPAN #4	TEST SPAN #5
INITIAL REFERENCE TESTING	BRIDGE SPAN 245	BRIDGE SPAN 246	BRIDGE SPAN 247	BRIDGE SPAN 248	BRIDGE SPAN 249
MATLAB CHEMICAL ANALYSIS CHLORIDE CONTENT (percent)					
Sample #1 (1/4"-1/2") Sample #2 (1/2"-1")					
ASTM C 876 HALF CELL POTENTIALS					
60' Spans, 5" Test Grid 48 Reading Average (volt DC)					
ASTM C 1202 CHLORIDE PENETRABILITY					
Core #1 (coulombs/rating) Core #2 (coulombs/rating)					
TESTING OF OVERLAY CONCRETE	LOT #7	LOT #10	LOT #8	LOT #11	LOT #9
DATE OF CONCRETE PLACEMENT	08/20/97	08/26/97	08/21/97	08/27/97	08/22/97
CONCRETE TEMPERATURE (°F)	86°	87°	87°	88°	86°
SLUMP (inches)	4.00"	3.75"	4.50"	3.00"	4.75"
AIR CONTENT (percent)	4.00%	4.25%	4.50%	4.50%	4.50%
ASTM C 39 24 HR COMPRESSIVE STRENGTH					
cylinder #1 psi	3416	2854			
cylinder #2 psi	3251	2278			
cylinder #3 psi	3598	2972			
average psi	3422	2702			
28 DAY COMPRESSIVE STRENGTH					
cylinder #1 psi	6972	7040			
cylinder #2 psi	6834	6613			
cylinder #3 psi	6830	6980			
average psi	6879	6878			
ASTM C 78 24 HR FLEXURE STRENGTH					
beam #1 psi	469	435			
beam #2 psi	466	412			
beam #3 psi	451	384			
average psi	462	410			
28 DAY FLEXURE STRENGTH					
beam #1 psi	798	815			
beam #2 psi	774	816			
beam #3 psi	790	743			
average psi	787	791			
ASTM C 496 28 DAY SPLITTING TENSILE					
cylinder #1	532	353			
cylinder #2	610	310			
cylinder #3	597	446			
average	580	370			
ASTM C 1202 28 DAY PENETRABILITY					
core #1 coulombs/rating	1974/LOW	2139/MOD			
core #2 coulombs/rating	2002/MOD	1574/LOW			
core #3 coulombs/rating	2592/MOD	2192/MOD			
core #4 coulombs/rating	1793/LOW	1978/LOW			
average coulombs/rating	2090/MOD	1971/LOW			
CI 503R ENSILE BOND STRENGTH					
core #1 psi/type failure					
core #2 psi/type failure					

DESCRIPTION	TEST SPAN #1	TEST SPAN #2	TEST SPAN #3	TEST SPAN #4	TEST SPAN #5
INITIAL REFERENCE TESTING	BRIDGE SPAN 245	BRIDGE SPAN 246	BRIDGE SPAN 247	BRIDGE SPAN 248	BRIDGE SPAN 249
MATLAB CHEMICAL ANALYSIS CHLORIDE CONTENT (percent) Sampled 07/11/97 Sample #1 (1/4"-1/2") Sample #2 (1/2"-1")	0.03 0.00	0.02 0.00	0.03 0.00	0.02 0.01	0.02 0.00
ASTM C 876 HALF CELL POTENTIALS Bridge Tested 07/16/97 60' Spans, 5" Test Grid 48 Reading Average (volt DC)	0.086	0.083	0.063	0.038	0.096
ASTM C 1202 CHLORIDE PENETRABILITY Cores drilled 07/11/97 Core #1 (coulombs/rating) Core #2 (coulombs/rating)	2460/MOD 2131/MOD		1148/LOW 1418/LOW		1944/LOW 1866/LOW
TESTING OF OVERLAY CONCRETE	LOT #2	LOT #5	LOT #3	LOT #6	LOT #4
DATE OF CONCRETE PLACEMENT	07/29/97	08/07/97	07/30/97	08/08/97	08/01/97
CONCRETE TEMPERATURE (°F)	94°	89°	87°	85°	85°
SLUMP (inches)	4.00"	4.00"	5.00"	4.50"	3.50"
AIR CONTENT (percent)	3.5%	4.5%	3.5%	4.5%	3.5%
ASTM C 39 24 HR COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi		2499 2607 2439 2515	3069 3082 3070 3074	2538 2641 2617 2599	
28 DAY COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi		6045 5784 5931 5920	7428 6438 7233 7033	7596 7581 7681 7619	
ASTM C 78 24 HR FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi		434 441 439 438	456 423 420 433	443 397 441 427	
28 DAY FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi		713 718 741 724	795 891 804 830	809 819 858 829	
ASTM C 496 28 DAY SPLITTING TENSILE cylinder #1 cylinder #2 cylinder #3 average		392 423 318 378	443 421 479 448	311 525 609 482	
ASTM C 1202 28 DAY PENETRABILITY core #1 coulombs/rating core #2 coulombs/rating core #3 coulombs/rating core #4 coulombs/rating average coulombs/rating		1900/LOW 1760/LOW 1615/LOW 1793/LOW 1767/LOW	1463/LOW 1400/LOW 1552/LOW 1856/LOW 1568/LOW	936/V.LOW 978/V.LOW 1406/LOW 1152/LOW 1118/LOW	
ACI 503R TENSILE BOND STRENGTH Tested xx/xx/xx core #1 psi/type failure core #2 psi/type failure					

DESCRIPTION	TEST SPAN No. 1	TEST SPAN No. 2	TEST SPAN No. 3	TEST SPAN No. 4
INITIAL REFERENCE TESTING				
MATLAB CHEMICAL ANALYSIS				
CHLORIDE CONTENT (percent)				
Sampled 07/10/97				
Sample #1 (1/4"-1/2")	0.65	0.72	0.13	0.29
Sample #2 (1/2"-1")	0.60	0.52	0.06	0.37
ASTM C 876				
Half Cell Potentials				
Bridge Tested 07/15/97				
60' Spans, 5' Test Grid				
Average of 33 Readings				
	0.165	0.131	0.236	0.254
ASTM C 1202				
CHLORIDE PENETRABILITY				
Cores drilled 07/10/97				
Core #1 (coulombs/rating)	3026/MODERATE			2024/MODERATE
Core #2 (coulombs/rating)	3294/MODERATE			
TESTING OF OVERLAY CONCRETE				
	LOT #19	LOT #18	LOT #13	LOT #14
DATE OF OVERLAY POUR	10/03/97	09/30/97	09/08/97	09/12/97
CONCRETE TEMPERATURE (°F)	79°	82°	87°	90°
SLUMP (inches)	4.00"	4.00"	4.50"	3.25"
AIR CONTENT (percent)	5.00%	3.00%	4.25%	5.00%
ASTM C 39				
24 HR COMPRESSIVE STRENGTH				
cylinder #1 psi		3717	1116	3082
cylinder #2 psi		3791	404	3362
cylinder #3 psi		3763	960	3594
average psi		3757	827	3346
*Concrete not properly mixed at sampling.				
28 DAY COMPRESSIVE STRENGTH				
cylinder #1 psi		6845	6037	6833
cylinder #2 psi		7948	6675	6739
cylinder #3 psi		7805	5855	7257
average psi		7533	6189	6943
ASTM C 78				
24 HR FLEXURE STRENGTH				
beam #1 psi		426	354	452
beam #2 psi		425	323	484
beam #3 psi		426	442	505
average psi		426	373	480
28 DAY FLEXURE STRENGTH				
beam #1 psi		904	728	802
beam #2 psi		861	822	802
beam #3 psi		818	766	827
average psi		861	772	811
ASTM C 496				
28 DAY SPLITTING TENSILE				
cylinder #1		345	424	333
cylinder #2		398	411	552
cylinder #3		372	437	475
average		372	424	454
ASTM C 1202				
28 DAY PENETRABILITY				
core #1 coulombs/rating		1171/LOW	1504/LOW	1361/LOW
core #2 coulombs/rating		1141/LOW	1361/LOW	1104/LOW
core #3 coulombs/rating		1286/LOW	1129/LOW	1455/LOW
core #4 coulombs/rating		1111/LOW	1108/LOW	1562/LOW
average coulombs/rating		1177/LOW	1276/LOW	1370/LOW
CI 503R				
TENSILE BOND STRENGTH				
core #1 psi/type failure				
core #2 psi/type failure				

DESCRIPTION	TEST SPAN No. 5	TEST SPAN No. 6	TEST SPAN No. 7	TEST SPAN No. 8
INITIAL REFERENCE TESTING				
MATLAB CHEMICAL ANALYSIS CHLORIDE CONTENT (percent) Sampled 07/10/97 Sample #1 (1/4"-1/2") Sample #2 (1/2"-1")	0.75 0.33	0.24 0.39	0.37 0.19	0.37 0.14
ASTM C 876 Half Cell Potentials Bridge Tested 07/15/97 60' Spans, 5' Test Grid Average of 33 Readings	0.188	0.287	0.311	0.278
ASTM C 1202 CHLORIDE PENETRABILITY Cores drilled 07/10/97 Core #1 (coulombs/rating) Core #2 (coulombs/rating)	3326/MODERATE			1177/LOW 1884/LOW
TESTING OF OVERLAY CONCRETE				
	LOT #12	LOT #15	LOT #16	LOT #17
DATE OF OVERLAY POUR CONCRETE TEMPERATURE (°F) SLUMP (inches) AIR CONTENT (percent)	09/04/97 86° 3.00" 4.00%	09/16/97 86° 4.00" 5.00%	09/19/97 86° 5.00" 4.5%	09/29/97 86° 3.00" 3.5%
ASTM C 39 24 HR COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi 28 DAY COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi				2979 2803 2933 2905 6867 6835 6874 6859
ASTM C 78 24 HR FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi 28 DAY FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi				488 488 497 491 681 821 847 783
ASTM C 496 28 DAY SPLITTING TENSILE cylinder #1 cylinder #2 cylinder #3 average				431 434 355 407
ASTM C 1202 28 DAY PENETRABILITY core #1 coulombs/rating core #2 coulombs/rating core #3 coulombs/rating core #4 coulombs/rating average coulombs/rating				1764/LOW 1946/LOW 1551/LOW 1600/LOW 1715/LOW
ACI 503R TENSILE BOND STRENGTH core #1 psi/type failure core #2 psi/type failure				

DESCRIPTION	TEST SPAN No. 1	TEST SPAN No. 2	TEST SPAN No. 3	TEST SPAN No. 4
INITIAL REFERENCE TESTING				
MATLAB CHEMICAL ANALYSIS CHLORIDE CONTENT (percent) Sampled 07/10/97 Sample #1 (¾"-¾") Sample #2 (¾"-1")				
ASTM C 876 Half Cell Potentials Bridge Tested 07/15/97 60' Spans, 5' Test Grid Average of 33 Readings				
ASTM C 1202 CHLORIDE PENETRABILITY Cores drilled 07/10/97 Core #1 (coulombs/rating) Core #2 (coulombs/rating)				
TESTING OF OVERLAY CONCRETE	LOT #26	LOT #25	LOT #27	LOT #22
DATE OF OVERLAY POUR	11/19/97	11/17/97	11/21/97	10/30/97
CONCRETE TEMPERATURE (°F)	65°	62°	62°	72°
SLUMP (inches)	4.00"	3.75"	4.50"	4.50"
AIR CONTENT (percent)	4.50%	3.75%	4.00%	4.00%
ASTM C 39 24 HR COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi				
28 DAY COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi				
ASTM C 78 24 HR FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi				
28 DAY FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi				
ASTM C 496 28 DAY SPLITTING TENSILE cylinder #1 cylinder #2 cylinder #3 average				
ASTM C 1202 28 DAY PENETRABILITY core #1 coulombs/rating core #2 coulombs/rating core #3 coulombs/rating core #4 coulombs/rating average coulombs/rating				
ACI 503R TENSILE BOND STRENGTH core #1 psi/type failure core #2 psi/type failure				

DESCRIPTION	TEST SPAN No. 5	TEST SPAN No. 6	TEST SPAN No. 7	TEST SPAN No. 8
INITIAL REFERENCE TESTING				
MATLAB CHEMICAL ANALYSIS CHLORIDE CONTENT (percent) Sampled 07/10/97 Sample #1 (1/4"-1/2") Sample #2 (1/2"-1")				
ASTM C 876 Half Cell Potentials Bridge Tested 07/15/97 60' Spans, 5' Test Grid Average of 33 Readings				
ASTM C 1202 CHLORIDE PENETRABILITY Cores drilled 07/10/97 Core #1 (coulombs/rating) Core #2 (coulombs/rating)				
TESTING OF OVERLAY CONCRETE	LOT #24	LOT #28	LOT #23	LOT #20
DATE OF OVERLAY POUR	11/07/97	10/28/97	11/04/97	10/21/97
CONCRETE TEMPERATURE (°F)	68°	76°	74°	84°
SLUMP (inches)	3.00"	4.50"	3.75"	3.50"
AIR CONTENT (percent)	4.50%	4.75%	4.50%	4.50%
ASTM C 39 24 HR COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi		1834 1861 1757 1817	2949 2986 3048 2994	2722 2931 2917 2857
28 DAY COMPRESSIVE STRENGTH cylinder #1 psi cylinder #2 psi cylinder #3 psi average psi		8163 8455 8601 8406	6740 8303 5004 6683	7989 7861 8118 7989
ASTM C 78 24 HR FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi		234 224 173 210	284 309 365 319	563 541 560 555
28 DAY FLEXURE STRENGTH beam #1 psi beam #2 psi beam #3 psi average psi		864 805 756 808	844 871 876 864	941 941 920 934
ASTM C 496 28 DAY SPLITTING TENSILE cylinder #1 cylinder #2 cylinder #3 average		575 613 577 588	349 504 352 402	562 423 485 490
ASTM C 1202 28 DAY PENETRABILITY core #1 coulombs/rating core #2 coulombs/rating core #3 coulombs/rating core #4 coulombs/rating average coulombs/rating		1351/LOW 1228/LOW 1401/LOW 1201/LOW 1295/LOW	1182/LOW 1260/LOW 1259/LOW 1269/LOW 1242/LOW	1170/LOW 963/V.LOW 1177/LOW 1131/LOW 1110/LOW
ACI 503R TENSILE BOND STRENGTH core #1 psi/type failure core #2 psi/type failure				

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
LOUISIANA TRANSPORTATION RESEARCH CENTER
Concrete Research Laboratory

TENSILE BOND STRENGTH OF OVERLAY MATERIALS
ACI 503R

LAB NO. : C-2146

DATE OF TEST: 01/29/98

PROJECT : 97-2C, THIN BONDED OVERLAY AND SURFACE LAMINATES OF BRIDGES

MATERIAL: I-10, BONNET CARRE SPILLWAY, RIGHT LANE, EASTBOUND

SPAN No.- SAMPLE No.	FROM START	FROM CURB	DATE OF OVERLAY	AGE DAYS	CROSS SEC. AREA SQ. IN.	STRESS AT FAILURE LBS	STRESS AT FAILURE PSI	TYPE FAILURE
1-1	13'	4'	07/29/97	184	12.56	750	60	ADHESIVE
1-2	33'	4"	07/29/97	184	12.56	1000	80	ADHESIVE
3-1	13'	4'	07/30/97	183	12.56	1850	147	COHESIVE
3-2	23'	4'	07/30/97	183	12.56	1550	123	ADHESIVE
5-1	14'	4'	08/01/97	182	12.56	1850	147	COHESIVE
5-2	43'	4'	08/01/97	182	12.56	1950	155	COHESIVE

NOTE: Adhesive Failure: Failure between cap and epoxy or failure between epoxy and overlay.
 Cohesive Failure: Failure between overlay and original pavement.

VISUAL OBSERVATIONS

- 1-1 : Scaling type failure between epoxy adhesive and surface of overlay. Some overlay surface material removed. Core removed manually. Separation of original pavement surface. Some aggregate failure visible.
- 1-2 : Failure between epoxy adhesive and pipe cap. Core removed manually. Separation of original pavement surface. Some aggregate failure visible.
- 3-1 : Failure of old pavement at overlay. Some aggregate failure visible.
- 3-2 : Failure between epoxy adhesive and pipe cap. Core removed manually. Separation of original pavement surface. Some aggregate failure visible.
- 5-1 : Failure of old pavement at overlay. Some aggregate failure visible.
- 5-2 : Failure of old pavement at overlay. Some aggregate failure visible.

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
LOUISIANA TRANSPORTATION RESEARCH CENTER
Concrete Research Laboratory

**TENSILE BOND STRENGTH OF OVERLAY MATERIALS
ACI 503R**

LAB NO. : C-2145

DATE OF TEST: 02/12+13/98

PROJECT : 97-2C, THIN BONDED OVERLAY AND SURFACE LAMINATES OF BRIDGES

MATERIAL: US 90, BAYOU DES ALLEMANDS BRIDGE, LEFT LANE, EASTBOUND

SPAN No. - SAMPLE No.	FROM START	FROM CURB	DATE OF OVERLAY	AGE DAYS	CROSS SEC. AREA SQ. IN.	STRESS AT FAILURE LBS	STRESS AT FAILURE PSI	TYPE FAILURE
1-1	10'	5'	10/03/97	132	12.56	1450	115	COHESIVE
1-2	13'	5"	10/03/97	132	12.56	1600	127	COHESIVE
3-1	12'	5'	09/08/97	161	12.56	500	40	COHESIVE
3-2	15'	5'	09/08/97	162	12.56	1650	131	ADHESIVE
5-1	9'	5'	09/04/97	166	12.56	1550	123	ADHESIVE
5-2	11'	5'	09/04/97	166	12.56	1850	147	ADHESIVE
7-1	4'	5'	09/19/97	147	12.56	1250	100	ADHESIVE
7-2	6'	5'	09/19/97	147	12.56	1300	104	ADHESIVE

NOTE: Adhesive Failure: Failure between cap and epoxy or failure between epoxy and overlay.
Cohesive Failure: Failure between overlay and original pavement.

VISUAL OBSERVATIONS

Span 1 Cores average depth of 2". Core drilled for ASTM C1202 seperated at overlay removing top of old concrete and covering 95% of core bottom with visible aggregate failure.

1-1 : Failure of old pavement at overlay. 90% of core bottom, old pavement, aggregate failure visible.

1-2 : Failure of old pavement at overlay. 85% of core bottom, old pavement, large aggregate failure visible.

Span 3 Cores average depth of 1½". Core drilled for ASTM C1202 seperated at overlay removing top of old concrete and covering 100% of core bottom with visible aggregate failure.

3-1 : Failure of old pavement at overlay. 25% of core bottom, old pavement, aggregate failure visible.

3-2 : Failure between epoxy adhesive and pipe cap. Core removed manually. Separation at original pavement surface with 60% of old pavement on core bottom. Aggregate failure visible.

Span 5 Cores average depth of 2¼" and difficult to remove. Core drilled for ASTM C1202 seperated at overlay removing top of old concrete and covering 25% of core bottom with visible aggregate failure.

5-1 : Failure between epoxy adhesive and pipe cap. Core removed manually but difficult causing damage to core surface. Separation at original pavement surface with 60% of old pavement on core bottom. Aggregate failure visible.

5-2 : Failure between epoxy adhesive and pipe cap. Attempt to remove core manually unsuccessful. Core destroyed. Unable to break bond to original pavement surface.

Span 7 Cores average depth of 2¼". Core drilled for ASTM C1202 difficult to remove with surface damage and failure of overlay material with no old pavement removed.

7-1 : Failure between epoxy adhesive and concrete overlay. Core removed manually. Separation at old pavement with aggregate failure visible. Steel rebar exposed.

7-2 : Failure between epoxy adhesive and pipe cap. Core removed manually. Separation at original pavement surface with 90% of old pavement on core bottom. Aggregate failure visible.

CONCLUSIONS

Thin bonded concrete overlay on this job appears to have excellent bond with the old pavement. In most cores difficulty was encountered during removal with the old concrete failing.

Control Section = 005 08 District = 02 Parish = St. Charles Route = U.S. 0090

Blank Tire

Control Tests

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
0.09	24.10
0.10	24.40
0.10	24.00
0.14	24.30
0.14	23.40
0.14	24.20

Average Skidnumber = 24.07

Beginning Logmile of Test Section = 0.0

Ending Logmile of Test Section = 0.1

Control Section = 005 08 District = 02 Parish = St. Charles Route = U.S. 0090

Blank Tire

Inside Test Section

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
0.01	20.10
0.01	20.20
0.01	20.10
0.05	25.10
0.05	25.40
0.05	23.00

Average Skidnumber = 22.32

Beginning Logmile of Test Section = 0.0

Ending Logmile of Test Section = 0.1

Control Section = 005 08 District = 02 Parish = St. Charles Route = U.S. 0090

Wetted Tire

Control Tests

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
0.09	44.60
0.10	44.40
0.10	44.80
0.14	43.90
0.14	45.80
0.14	47.30

Average Skidnumber = 45.13

Beginning Logmile of Test Section = 0.0

Ending Logmile of Test Section = 0.1

Control Section =005 08

District =02

Parish = St. Charles

Route =U.S. 0090

Treaded Tire

Inside Test Section

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
0.01	42.60
0.01	42.30
0.01	43.70
0.05	37.20
0.05	37.30
0.05	41.20

Average Skidnumber =

40.72

Beginning Logmile of Test Section = 0.0

Ending Logmile of Test Section = 0.1

Control Section = 450 14 District = 02 Parish = St. Charles Route = I-0010
Treaded Tire
Inside Test Section

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
3.03	42.70
3.04	42.70
3.04	42.40

Average Skidnumber = 42.60

Beginning Logmile of Test Section = 3.03
Ending Logmile of Test Section = 3.10

Control Section = 450 14 District = 02 Parish = St. Charles Route = I-0010
Blank Tire
Inside Test Section

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
3.04	25.50
3.04	26.70
3.04	25.70

Average Skidnumber = 25.97

Beginning Logmile of Test Section = 3.03

Ending Logmile of Test Section = 3.10

Control Section = 450 14 District = 02 Parish = St. Charles Route = I-0010
Treaded Tire
Control Test

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
3.10	40.50
3.10	39.80
3.10	38.60

Average Skidnumber = 39.63

Beginning Logmile of Test Section = 3.03
Ending Logmile of Test Section = 3.10

Control Section = 450 14

District = 02

Parish = St. Charles

Route = I-0010

Blank Tire

Control Test

<u>LOGMILE</u>	<u>SKIDNUMBER</u>
3.10	22.80
3.10	21.90
3.10	21.90

Average Skidnumber =

22.20

Beginning Logmile of Test Section = 3.03

Ending Logmile of Test Section = 3.10

I-10 BONNETT CARRE SPILLWAY, MICRO SILICA BRIDGE DECK OVERLAY
FWD READINGS IN MILS AT THE CENTER OF THE LOAD PLATE (MAXIMUM DEFLECTION)


LOCATION	PRE-OL (7-10-97)	AFTER OL (8-11-97)
A-1	9.74	8.88
A-2	15.57	15.70
B-1	8.54	8.62
B-2	14.42	14.45
C-1	8.56	7.70
C-2	13.85	14.88
D-1	8.16	8.20
D-2	16.91	15.34
E-1	8.86	8.48
E-2	18.18	15.96

U.S. 90 - DES ALLEMANDS - MICRO SILICA BRIDGE DECK OVERLAY
FWD READINGS IN MILS AT THE CENTER OF THE LOAD PLATE (MAXIMUM DEFLECTION)

LOCATION	PRE-OL (7-11-97)	AFTER OL (2-12-98)
B-1	18.94	20.78
B-2	23.56	25.90
C-1	23.77	20.20
C-2	27.61	27.08
D-1	18.76	18.61
D-2	31.48	24.16
E-1	19.96	18.69
E-2	26.89	25.81
F-1	33.12	17.87
F-2	37.84	23.06
G-1	19.54	20.53
G-2	39.59	25.34


LOCATION 1 IS 5 FT AHEAD OF JOINT, LOCATION 2 IS 30 FT AHEAD OF JOINT

**I-10 MICRO SILICA BRIDGE DECK OVERLAY
MAX FWD DEFL AT MID SLAB**



U.S. 90 MICRO SILICA BRIDGE DECK OVERLAY

MAX FWD DEFL AT MID SLAB



This public document is published at a total cost of \$667.83. One hundred copies of this public document were published at a cost of \$382.83. The total cost of all printings of this document including reprints is \$667.83. This document was published by Louisiana State University, Graphic Services, 3555 River Road, Baton Rouge, Louisiana 70802, to report and publish research findings of the Louisiana Transportation Research Center as required in R.S.48:105. This material was printed in accordance with standards for printing by state agencies established pursuant to R.S.43:31. Printing of this material was purchased in accordance with the provisions of Title 43 of the Louisiana Revised Statutes.